



Govt. of Bihar
MUZAFFARPUR INSTITUTE OF TECHNOLOGY,
MUZAFFARPUR, BIHAR – 842003
(Under the Department of Science & Technology, Govt. of Bihar, Patna)

Notice. No.: 724/TEQIP-III

Dated: 22/07/2019

Notice

M.I.T. Muzaffarpur is in the process of refurbishment of different department under TEQIP-III .
Proposed civil/electric works are as follows:-

1. Package Name: MITM/INSTITUTIONAL/LAB REFURBISHMENT

A. Detail of civil work of renovation of old Computer Center and proposed work.

S.No.	Description of work	Quantity	Unit
1	Dismantling of Work	2063	Sqm
2	Wall Plaster and Repairing	1100	Sqm
3	Vetrified Tiles 2x2	287	Sqm
4	Glazed wall tiles	225	Sqm
5	MS Gril	270	Kg
6	Aluminum door and sliding door partition all completed job	488	Sqft
7	Aluminum window two track	84	Sqft
8	Aluminum partition work in computer cabin	402	Sqft
9	Carpentering work with 12 mm laminated board approved brand for forty number computer cebin	80	Sqm
10	Wall putti in side of computer building	700	Sqm
11	Primer in side of computer building	700	Sqm
12	Distempering in side of computer building	700	Sqm
13	Wall putti outside computer building	400	Sqm
13	Primmer outside of computer building	400	Sqm
14	Weather coat outside of computer building	400	Sqm
15	Grill Painting with enamel paint	100	Sqm
16	Wooden enamel paint	115	Sqm
17	Repairing of APP above roof at computer building	277	Sqm
18	Brick Flat Soling	130	Sqm
19	P.C.C	15	cum
20	Chequered tiles	185	Sqm
21	Water tank	1000 ltr	Nos.
22	Brick work with Mortar(1:6)	30	cum
23	Plaster and Painting	50	Sqm
24	RCC work	2.5	cum
25	Steel 10mm	100	Kg
26	Commode with all Fittings	1	Nos.
27	Wash basin with all fittings	1	Nos.
28	Urinal with all fittings	1	Nos.
29	Rain water pipe and upvc pipe	100	RMT

30 Electrical Work

30.01	Metal Pannel	4ft*3ft*1ft	24
30.02	MCC B	200 A 4 Pole	1
30.03	MCC B	100A, 4 Pole	1
30.04	MCB	63 A 4 Pole	1
30.05	MCB	40 A 4 Pole	1
30.06	MCB	63 A 2 Pole	1
30.07	MCB	16 A2 Pole	2
30.08	MCB	6 A 2 Pole	1
30.09	MCB	20 A 1 Pole	15
30.10	Encloure	4 Pole	1
30.11	Encloure	2 Pole	3
30.12	Baseball	63A	2
30.13	MCB	6 way	4
30.14	MCB	10A (SP)	30
30.15	AC Box	20A	15
30.16	Box	6 Module	50
30.17	Socket	10 Module	120
30.18	Switch	10 Module	120
30.19	Plate	6 Module	50
30.20	Inner Plate	6 Module	50
30.21	Socket	20A	20
30.22	Switch	20A	20
30.23	Box	3 Module	20
30.24	Cover	3 Module	20
30.25	Inner Plate	3 Module	20
30.26	Box	12 Module	10
30.27	Inner Plate	12 Module	10
30.28	cover	12 Module	10
30.29	Fan Regulator	Moduler	1100
30.30	Coil	0.75mm	2
30.31	Coil	1.mm	7
30.32	Coil	1.5 mm	7
30.33	Coil	2.5 mm	3
30.34	Coil	4 mm	4
30.35	Coil	6 mm	4
30.36	Almunim core	150 mm	75 meter
30.37	Thimble	150 mm	8
30.38	Almunim core	50 mm	20 meter
30.39	Flexible Pipe	1 inch	100 piece
30.40	Pipe	1 inch	100 piece
30.41	Band	1 inch	48
30.42	Juction Box	1 inch	48
30.43	Kanti steel	1 inch	200
30.44	Tee	1 inch	24
30.45	Sidle	1 inch	160
30.46	C. Rose	6A Moduler	36
30.47	Button Holder	6A	24 Pice

30.48	LED Light	45 watt	4
30.49	LED Light	2ft*2ft(40 watt)	8
30.50	Tube Light	18 watt	20 piece
30.51	LED Bulb	11 watt	12 piece
30.52	Fan Regulator	6A	15 piece
30.53	Volt Meter Digital	90 mm	1 piece
30.54	Ampere Meter	90 mm	2 piece
30.55	CT Coil	300/5A	3 piece
30.56	Indicator	6A	6 piece
30.57	Networking Pipe	1 inch 2mm	50 piece
30.58	Networking cable	2.5mm	5 Quire
30.59	Networking Junction Box	16A	50 piece

B. Annexe of Conference Room:

	Description of work	Quantity	Unit
I	Dismantling works	90	Sqm
II	Wall Putti	252	Sqm
III	Primer Work	255	Sqm
IV	Dismantling pring work First Quality	255	Sqm
V	Enamel Painting	40	Sqm

C. Adjoining room of civil engg. Dept.

	Description of work	Quantity	Unit
I	Dismantling works	172	Sqm
II	Wall Putti	708	Sqm
III	Primmer Works	708	Sqm
IV	Dismantling Works	708	Sqm

V	Aluminum Sliding in front of Principal Chamber south side three track	446	Sqft
VI	Aluminum door with partition passage east side	202	Sqft
VII	Grill work	80	Kg
VIII	Aluminum partition cabin for computer chamber in office	112	Sqft
IX	Aluminum Counter Glass Fitting and partition work with 5 nos. drawal	1	Nos.
X	Glass 5mm	25	Sqft
XI	Providing and laying granite fitting for in front of administrative building stems pillar and side wall	40	Sqm
XII	Colored aluminum partition work in front of administrative building	500	Sqft
XIII	Wall Putti in front of administrative building	75	Sqm
XIV	Primmer Works in front of administrative building	75	Sqm
XV	Weather Coat paint	75	Sqm

D. Library Room

I	Aluminum door	161	Sqft
II	Aluminum window two track	108	Sqft

E. Leather Technology Department

RCC Work	1	cum
Steel 10mm	30	kg
Brick work	32	Sqft
Aluminum partition work in leather workshop	502	Sqft
PCC in front of leather building	6	cum
Shade in front of leather building	40	Sqft
Wall putti	250	Sqm
Primer	250	Sqm
Dismantling of Work	250	Sqm

F. Annexe of workshop

II	Grade Beam 5 Nos. Platform M25	5	cum
III	Reinforcement 5 nos. Platform 10 mm	600	Kg
IV	Brick flat soling	50	Sqm
V	Brick work	15	cum
VI	Plaster paint	56	cum
VII	Earth work	80	cum
VIII	Shade	60	Sqmt

Details specification will be given in the invitation letter.

Interested suppliers/bidders are required to give the following information/documents on principal@mitmuzaffarpur.org latest by 29.07.2019 so that invitation for bidding process can be initiated through PMSS.

1. Supplier Name :
2. Address(With Pin Code):
3. Contact Person Name :
4. E-Mail-ID:
5. Mobile No.:
6. TIN/GST No.
7. PAN No.

Principal
MIT Muzaffarpur

22/7/19
Rohit
Z. Anon